

Khyber Pakhtukhwa Community-Driven Local Development (CDLD) Technical Supervision and Inspection Plan

Visit no.	Purpose
1.	Visit to check the standards and quality of materials procured (or samples of the materials delivered at site) for the project to ensure the pre-execution quality control measures and technical inputs.
2.	Giving/checking the layouts physically on site of various components of the project (as per the approved design and standards), for initiation of physical work.
3.	Monitoring and supervision of the physical work on site after 15% to 20% of the work done (two to three weeks after the initiation of the work) to check and verify both the quality and quantity at site and necessary required technical inputs for work ahead and also to monitor/measure the work progress as per agreed work schedule.
4.	Measurement of work done at site for validation of quality and quantity for next (second) installment
5.	Monitoring and supervision of the physical work on site after 45% to 50% of the work done to check and verify both the quality and quantity at site and also to monitor work progress to ensure timely completion
6.	Monitoring and supervision of the physical work on site after 75 to 80% of the work done to check and verify both the quality and quantity at site and also to monitor/measure work progress to ensure timely completion
7.	Final measurement of work done at site for validation of quality and quantity for next (third) installment and for final completion certificate